



REPUBLIC OF THE PHILIPPINES  
DEPARTMENT OF NATIONAL DEFENSE  
**NATIONAL DEFENSE COLLEGE OF THE PHILIPPINES**  
Camp General Emilio Aguinaldo, Quezon City

19 November 2021

**SUPPLEMENTAL BID BULLETIN No. 008-21**

**Improvement of Access Roads and Ceremonial Grounds  
of the National Defense College of the Philippines**


This Supplemental Bid Bulletin is issued to inform prospective bidders of the following changes, modifications, amendments, or additional requirements that forms part of the Bidding Documents for the Improvement of Access Roads and Ceremonial Grounds of the National Defense College of the Philippines.

**MODIFICATIONS ON THE BIDDING DOCUMENTS**

REF	PARTICULARS	FROM	TO
Page 22	A. Scope of Works Item Nos: 2 (b & c);  3 (a,b & c);  4 (a)	2b. (stabbing, etc).  2c. Backfilling/leveling using garden soil including compaction  3a. Base preparation (Gravel bedding of 2' thick & compacted)  3b. Formworks  3c. Concreting at 3000 psi with 2.5m width and 3' thickness  4a. Construction of waddy includes shaping & planting of grass	2b. (staking, establish vertical control points including horizontal control and survey references points) 2c. Backfilling/leveling using garden soil including compaction on the approved top soil materials 3a. Base preparation (Gravel bedding of 2' thick & compacted using 3/8 gravel bedding) 3b. Formworks (Provide construction concrete expansion joints every 3m) 3c. Concreting at 3000 psi with 2.5m width and 3' thickness using 1 bagger mixer 4a. Construction of waddy includes shaping & planting of carabao

	<p>A. Scope of Works</p> <p>6b</p>	<p>6b. Carabao grass planting with a 4x4 cuttings</p>	<p>grass along the stretch of the waddy</p> <p>4c. Cross pipes laying of 6" diameter pvc drainage pipe at 5 meters interval</p> <p>5c. Slab on 8" thick at 3000 psi</p> <p>5d. Roof frame must be 2x6 tubular (Truss/support) and 2x6 C-purlins @ 0.6m o.c</p> <p>5e. Steel post must be tubular 2x6x1/4</p> <p>6b. Carabao grass planting with a 4x4 cuttings for the entire ground</p> <p>8. Trimming of trees</p> <p>9. Submission of As-built plan</p>
--	------------------------------------	---	--

For guidance and information of all concerned.

  
**CAPT ALDRIN C CUNA PN (Res), MNSA**  
 Executive Vice President  
 NDCP-BAC Chairperson